


92

8534

Survey  
5-97



Surveyed Sept 4<sup>th</sup> 1847 for John Kautzman  
 Survey No 9888. As follows;  
 Beginning at a blue oak, Sugar tree and Elm  
 (elm gone) in Greenville tract line at the South  
 East Corner of Jamison's and others Survey 9887  
 and run with said tract line N 80° E Crossing  
 one branch at 30 poles one at 106 poles and  
 one at 178 poles 380 poles to 2 Buck (both  
 gone then N 10° W 106 poles to branch 171 poles  
 to Mill Creek, 340 poles to Spring branch  
 210 poles to Stone then, S 80° W 200 poles  
 to the two Sugar trees and a buck N 70° W  
 Corner of said Jamison's Survey then  
 S E 440 poles to the Beginning  
 Containing 976<sup>7/10</sup> Acres  
 J Kautzman 3  
 Geo Kautzman 3  
 A. Harrison

8534

Thence S 1/2 W 72 poles to a stone in a field  
thence N 89 1/2 W 34 7/25 poles to a stake near a  
White Oak thence S 1/2 W 30 poles to a stake  
in a County road,

Dennis Conards describes as follows - Absolom is described as follows

- 1 S 1/2 W 72 poles
- 2 N 89 1/2 W 34 7/25 "
- 3 S 1/2 W 30 "
- 4 S 81 1/4 E 22 "
- 5 S 89 1/2 E 98 5/25 "
- 6 N 1/2 E 53 18/25 "
- 7 N 89 1/2 W 17 22/25 "
- 8 N 1/2 E 53 18/25 "
- 9 N 89 1/2 W 70 3/25 "

- 1 S 1/2 W 72 poles
- 2 N 89 1/2 W 34 7/25 "
- 3 S 1/2 W 30 "
- 4 N 81 1/4 W 38 7/25 "
- 5 N 1/2 E 107 10/25 "
- 6 S 89 1/2 E 70 5/25 "

The foregoing descriptions both begin at the same place i.e. where the last named line commences -

D. Conard  
A. D. Jones

O. Hayes Sur. L. C. C.

Survey No. 630

8534

Surveyed June 21-22/48 for John Kautzman of Rush creek township L. County O. Military Survey No. 9888 on the waters of Mill creek as follows "to wit" Beginning at the N.E. corner of said Survey at a Stone thence S 79 W 100.40 chains crossing a road at 69 chs to a stake from which a Sugar tree 16 In. dia bears N 25 1/2 E 9 links and a do. 10 In. dia S 33 1/2 E 16 1/2 links distant thence S 11 E 100 chs crossing the aforesaid road at 55 chs to a stake from which a blue Ash 16 In. dia bears N 54 E 27 links and a hickory 5 In. dia N 47 1/2 W 9 links dist.

thence  $N 79^{\circ} E$  100 chs. passing along an exceeding high bank to a stake in a field thence  $N 11^{\circ} W$  100. ch. crossing a brook at 47.50 chains and spring brook at 260 poles to place of beginning containing 1002 Acrey

Subdivided same as follows.

Beginning at a stake in the North line of said Survey (at the centre) from which a Sugar 20 I. S. bears  $S 73^{\circ} E$  26 and Hickory 18 I. S.  $N 77^{\circ} W$  8 links distant thence  $S 11^{\circ} E$  100 chs. passing stake 33.58 chs ~~corner~~ to creek at 55 chs. and deep ravine at 99 chains to a stake in the centre of South line of said Survey Then divided said Survey by two lines running Easterly through same

as follows 1st. Beginning at a stake in the West line of said survey 33.58 chs. from the S.W. corner of the same from which a sugar 15 I. S. bears  $S 4^{\circ} E$  8 and sugar 12 I. S.  $N 32^{\circ} W$  14 links distant thence  $N 79^{\circ} E$  100 chs. passing Ironwood 4 I. S. at 50 chs. (corner to John Roberts, John Kautzman, George Kautzman and Peter Kautzman) to a stake in the East line of said Survey from which a Bur Oak 30 I. S. bears  $S 6^{\circ} W$  9 links. Second line runs as follows Beginning at a stake in the West line of said Survey from which an Elm 18 I. S. bears  $S 37^{\circ} E$  29 and Beech  $N 77^{\circ} E$  32 links distant thence  $N 79^{\circ} E$  100 chs. crossing Jamesfield road at 23.50 chs. passing a small beech at 50 chs. (corner of John, George Barney and Old man Kautzman) to a stake in the E. line of said Survey 33.58 chs. S.W. of the N.E. <sup>corner</sup> of the same John Kautzman & Peter Kautzman chs. ers. O. Hayes Sur. L. C. Ohio.

8537

Survey No 631

Surveyed June 23/48 for Jesse Roberts part of Military Survey No. 13203 on the Waters of Boker Creek as follows  
 Beginning at Lawson Riddells S.E. corner at a Buckeye Buchard cherry thence S 10° E 155 poles crossing a road at 80 poles a branch at 128 poles to two Beeches Original corner of said Block (No 13203) thence S 78° W 103 3/4 poles crossing a branch at 25 poles to a Beech and Small Sugar thence N 10° W 155 poles crossing a branch at 20 and one at 51 and a road at 74 poles to a Buchard Buckeye bush thence N 78° E 103 3/4 poles to the beginning containing 100 Acres

Lawson Riddell ch. ers.  
 C Hayes Sur. L.C.C.

8534

Survey No 632

July 15th 1848

In pursuance of the following notice I proceeded on the above date to take deposition and establish the South East corner of military survey No 9888 -  
 Mr John Countryman

Sir,

You will take notice that on the 15th day of July A.D. 1848 I (pro) will take testimony before Oam Hayes Surveyor of Logan County to establish the South East corner of Virginia Military Survey No 9888 in Logan county, which corner has been destroyed. The testimony will be taken and the lines of survey connected with said corner be run by said Surveyor and the

Corner established on the premises  
and at said corner, on the day and  
year aforesaid at which time and place  
you can attend with your testimony  
and cross examine the witnesses  
produced by us if you see proper  
June 24<sup>th</sup> 1848

Anderson Williams  
(Signed) Nathan Hockett  
Benja<sup>his</sup> M. Hodges  
mark

June 24<sup>th</sup> 1848 Subpoena issued for the  
following persons as witnesses for the  
applicants to wit. Jacob King, John Pro-  
ter, Henry Rosebrough and Sander  
Jacobs and delivered the same to  
Philip G. Johnson Constable of Rush-  
creek township Logan county O.

July 15/48 Subpoena returned Endorsed  
"Served by reading the within to  
Henry Rosebrough, John Proter and  
Jacob King" Philip G. Johnson Const-

Testimony of witnesses taken before me  
Oden Hayes Surveyor of Logan county  
on the 15<sup>th</sup> day of July A. D. 1848 at the  
South East corner of Virginia Military  
Survey N<sup>o</sup> 9888 in pursuance of the notice  
hereto attached and at the time and place  
therein mentioned present Nathan Hockett  
Anderson Williams Benja M. Hodges and  
John Cantzman at which time and place  
came John Proter Henry Rosebrough and  
Jacob King all of Logan county and of-

lawful age who being first duly sworn  
as hereafter certified depose as follows in  
answer to the interrogatories

Deas. By applicants  
John Prater,

Have you ever seen the  
marked trees standing at the South East  
corner of Virginia Military Survey #09888  
in Logan County, and if so what and what  
kind of timber was it, and how were the  
trees marked?

Ans. I saw the corner that Mr Samuel  
Ruth showed when he (Ruth) and I  
traded land, Ruth traded the land to  
me adjoining the <sup>said</sup> corner for another lot  
on Rush Creek Logan County Ohio.

I saw the corner in 1832. It was a beech  
stump broke off up some 8 or 10 feet high  
don't remember height distinctly. It  
was marked with hacks seemed to be  
made with an ax or hatchet.

Q by same, How near did you live to said  
corner after you traded land with Ruth,  
and did you ever see it after it was  
first shown to you, and how often did  
you see it afterwards?

Ans. I lived about 80 poles from said corner  
and I saw it frequently - I do not know  
how often.

Q by same. Can you now point out the  
place where the corner tree <sup>or stump</sup> formerly  
stood, and if so where was it?

Ans. I gave Benja W Hodges a lease on the land  
near the corner and he built a house near  
the corner after I showed it to him.

and I recollect the corner as being near the chimney of said Hodges' house, say not more than 3 rods, in a S. W. direction and within 16 1/2 feet of the ground I now point out

Q by same, Have you continued to reside in the neighborhood, and do you know whether the land adjoining has been improved and occupied to conform to this corner?

Ans. I have not, continued to reside in the neighborhood (and do not know how the land was improved)

(Signed) John Prater

Jacob King - Have you seen the corner trees standing at the South East corner of Va. Military Survey 9888 in Logan County and if so when, what kind of timber were they, and point out the place where they stood?

Ans. I never saw the trees standing - I saw the stump of One, and the other was blown down and the log was still laying - I saw the corner before there was any improvement made about (it) the corner - say about 18 or 20 years ago. It was shown to me by Samuel Ruth and Samuel Monjar and I saw it frequently, afterwards the timber was two Beeches marked as a corner and they stood near a little branch in the edge of the "fallen timber" and the

trees were not more than 4 or 5 rods from the aforesaid branch. And about the same time and noticed and followed a marked line from said corner northwardly some distance

Jacob King <sup>his</sup> mark  
Henry Rosebrough State

ever saw the corner tree at the South East corner of Military Survey No 9888 in Logan County and if so where when, was it and where did they stand?

Ans I was fetched once to carry chain for a Surveyor by the name of White some 25.016 years ago last Jan'y, or Feb'y, and we commenced at the South East corner of Military Survey No 9888 and we made a corner in the East line of said survey which was marked on a sugar tree that I recollect and there was a plain marked line from said sugar both northerly and southerly to the N.E. and S.E. corners of said survey - I do not remember the ground on which said trees stood the trees were both Beeches.

I By same

Did you ever run round or subdivide the survey since you first saw the corner and if so at whose request, and what was the length of the south line of the survey -?

Ans I did run round the survey (at the request of Mr Porterfield) as chain carrier and we found the South line of said survey only 380 poles long



I. By same,

Can you point out the Sugar tree corner made by Mr White in the East line of the Survey the first time you saw the S.E. corner of the Survey and if so where is it?

Ans. I can. It stands on the South bank of Mill creek and is now pointed out.

(Signed) Henry Rosebrough

I Oden Hayes County Surveyor of Logan county Ohio do hereby certify that the aforementioned John Prater, Jacob King and Henry Rosebrough were by me first duly sworn to testify the truth the whole truth, and nothing but the truth and that the foregoing depositions by them respectively subscribed were reduced to writing by me, and taken at the time and place specified in the foregoing notice,

In testimony whereof I have hereunto set my hand this 15th day of July in the year A.D. 1848.

O. Hayes, Sur. C., O.

In pursuance of the foregoing depositions and the old marked lines I established the S.E. corner of Virginia Military Survey No. 9888 N. 78° E. 380 poles from the S.W. corner of said Survey and S. 9 1/2° E. 400 poles from the N.W. corner of the same as nearly in the original Greenwell's Treaty line as possible and about 4 poles from the branch mentioned by Mr. King

in his testimony and near a small <sup>135</sup>  
 hickory bush, at which point I caused  
 a large stone to be planted in the pres-  
 ence of the following named persons -  
 John Prater, Andrew Roberts, B. Stan-  
 ton Esq, Henry Rosebrough, Wm D. Brun-  
 son, Jeremiah Hill, Eros Williams,  
 Samuel Searauff, -  
 William Callahan } ch.ers.  
 David Pugh }  
 O. Hayes Sur. L. C.

Survey N<sup>o</sup> 633 <sup>Surveyed Aug. 5<sup>th</sup> 1848</sup>  
 for Samuel M<sup>rs</sup> Beth the  
 South West quarter of Section 35. Town  
 5. Range 13 E. L. M. R. as follows -  
 Beginning at the S. W. corner of said  
 Section at a stone from which a  
 Burr Oak stump bears N 53 E 17 links  
 distant, thence N 1° E 160 1/2 poles to  
 a stone and stake, thence N 89 3/4 E  
 172 poles to a stake at the centre  
 of the Sect. thence S 1° W 160 1/2 poles  
 to a stone in the centre of the South  
 line of said Sect, thence S 89 3/4 W 171 1/4  
 poles to the place of beginning contain-  
 ing 172 Acres and 186 perches.

Saml M<sup>rs</sup> Beth }  
 John Stow } ch.ers.  
 April 3<sup>rd</sup> 1848 }  
 O. Hayes Sur. L. C.  
 Subdivided the foregoing gr. by ~~line~~  
 for Samuel M<sup>rs</sup> Beth and Shepard Green by  
 a line beginning at the middle of the S. line  
 thence N 1° E to the centre of that S. line of the same  
 S. Green } ch.ers.  
 O. Hayes Sur. L. C.