

Hull - Oldham Survey Stokes Township March 1964 1.39 Acres Tract A.

The following described tract in Stokes Township, Logan County, Ohio and being in V.M.S. 12276

Beginning at an iron in the center of State Route Number 702 and being station 38 plus 00 of said Road as shown on Logan County Engineer's Map K - 58

Thence with the center of State Route Number 702 S. 30° - 49' W. 68.00 feet to an iron.

Thence N. 50° - 16' W. 71.30 feet to an iron. The last described line being the north side of Robert F. Hall's 0.03 acre tract.

Thence S. 37° - 29' W. 42.20 feet to an iron in the north line of Earl H. Mareo's 0.07 acre tract.

Thence with the north line of said Mareo's tract N. 60° - 01' W. 20.50 feet to an iron in the State Line.

Thence with the State Line N. 7° - 00' E. 52.00 feet to an iron at monument number 4 of the State Line. Monument Number 4 being shown on Logan County Engineer's Map K - 58

Thence again with the State Line N. 5° - 58' W. 42.10 feet to an iron at monument Number 3 of the State Line.

Thence again with the State Line N. 29° - 29' E. 151.20 feet to an iron at monument Number 2 of the State Line.

Thence again with the State Line N. 33° - 56' E. 143.20 feet to an iron at monument Number 1 of the State Line.

Thence again with the State Line N. 40° - 53' E. 36.75 feet to an iron.

Thence with the south side of Spiler's 0.16 acre tract S. 52° - 55' E. 180.60 feet to an iron in the center of State Route Number 702.

Thence with the center of State Route Number 702 S. 40° - 06' W. 300.15 feet to the place of beginning.

The above described tract contains 1.39 acres.

The above described tract is shown on Logan County Engineer's Map S - 25.

cc
Logan County Engineer.



3665
ID-1
INDEXED ON MAP

Hull - Oldam Survey Stokes Township March 1964 0.48 Acre Tract B

The following described land in Stokes Township, Logan County, Ohio and being in V.M.S. 12276

Beginning at an iron in the center of State Highway Number 702 at Station 34 plus 37.60 as shown on Logan County Engineer's Map K - 58

Thence with the center of said State Route Number 702 S. 40° - 06' W. 16.75 feet to an iron.

Thence N. 57° - 47' W. 182.25 feet to an iron in the State Line.
(The said State Line is shown on Logan County Engineer's Map J - 4 - A.)

Thence with the State Line N. 40° - 53' E. 42.85 feet to an iron at the S.W. corner of Cecil F. Chevalier's 0.13 acre tract.

Thence S. 50° - 30' E. 86.50 feet to an iron.


Thence with the east side of a 20 foot Drive N. 40° - 10' E. 155.10 feet to an iron at the S.W. corner of W. Wayne Lowry's 0.07 acre tract.

Thence with the south side of said Lowery tract S. 45° - 24' E. 105.10 feet to the center of State Route Number 702.

Thence with the center of State Route Number 702 S. 43° - 56' W. 149.95 feet to the place of beginning.

The above described tract contains 0.48 of one acre and being the tract as shown on Logan County Engineer's Map S - 25

cc
Logan County Engineer.



10-2

Hull - Oldham Survey Stokes Township March 1964 1.19 Acres Tract C

The following described land in Stokes Township, Logan County, Ohio,
and being in V.M.S. 12276

Beginninh at an iron in the center of State Route Number 702.
at Station 38 plus 00 as shown on Logan County Engineer's Map K - 58

Thence with the center of State Route Number 702 S. 30° - 49' W. 84.00 feet
to an iron.

Thence S. 50° - 41' E. 95.30 feet to an iron. The last described line
being along the north side of K.P Holcomb's 0.07 acre tract.

Thence with the east side of said Holcomb's tract S. 30° - 49' W. ~~44.00~~ feet
to an iron.

Thence S. 50° - 41' E. 7.75 feet to an iron in the State Line. The State
Line is shown on Logan County Engineer's Map J - 4 - A.

Thence with the State Line N. 64° - 10' E. 27.50 feet to an iron at
monument Number 19.

Thence again with the State Line S. 83° - 30' E. 145.60 feet to monument
Number 20.

Thence again with the State Line S. 11° - 57' W. 74.00 feet to
monument Number 21.

Thence again with the State Line S. 38° - 03' E. 83.90 feet to an iron
in the west side of a 22 foot drive.

Thence with the west side of said 22 foot drive N. 34° - 45' E. 50.35
feet to an iron.

Thence with the south side of Robert Ballett's 0.07 acre tract
N. 53° - 32' W. 80.00 feet to an iron.

Thence N. 34° - 45' E. 80.00 feet to an iron. at S. Wright's N.W. corner.

Thence with the south side of a 0.14 acre tract N. 53° - 30' W. 80.00
feet to an iron.

Thence N. 34° - 48' E. 120.00 feet to an iron in the south side of a drive.

Thence with the south side of said Drive the following two courses and
distances. N. 48° - 41' W. 92.50 feet to an iron and N. 54° - 13' W. 98.30
feet to an iron in the center of State Route Number 702.

Thence with the center line of State Route Number 702 S. 40° - 06' W.
132.20 feet to the place of beginning.

The above described tract contains 1.19 acres and is shown on Logan
County Engineer's Map S - 25.

cc
Logan County Engineer.

INDEXED ON MAP

3565

ID-3

Hull Survey v.m.s. 12277 March 1964 0.07 Acre Tract D

The following described land in Stokes Township, Logan County, Ohio and being in V.M.S. 12277

Beginning at an iron pipe at State Monument Number 27 as shown on Logan County Engineer's Map J - 4 - A. Thence N. 47° - 21' W. 100.00 feet to an iron pipe at the N.W. side of a private right of way.

Thence with the N.W. side of said right of way N. 30° - 18' E. 229.00 feet to an iron pipe said pipe being the true beginning point of this survey.

Thence again with the N.W. side of said right of way N. 30° - 18' E. 50.00 feet to an iron at the S.E. corner of Merle E. Leininger's 0.07 acre tract.


Thence with the south side of said Leininger's tract N. 47° - 21' W. 64.15 feet to an iron in the east side of L.E.Hull's present 2.31 acre tract.

Thence with the east side of said Hull 2.31 acre tract S. 34° - 49' W. 49.40 feet to an iron.

Thence with the north side of Carrie M. Reynold's 0.08 acre tract S. 47° - 21' E. 68.10 feet to the place of beginning.

The above described tract contains 0.07 of one acre.

cc
Logan County Engineer.



1D-4

Hull - Oldham Survey Stokes Township March 1964 2.31 Acres Tract E.

The following described land in Stokes Township, Logan County, Ohio and
being in V.M.S. 12277 Tract E.

Beginning at an iron in the center line of State Route Number 702 and
being station 27 plus 41 of said State Highway and being shown on
Logan County Engineer's Map K - 58.

Thence with the center line of State Route Number 702 N. 22° - 02' E.
37.00 feet to an iron.

Thence with the south side of Erma Newland's 0.50 acre tract
S. 87° - 54' E. 237.40 feet to an iron.

Thence S. 34° - 00' W. 227.55 feet to an iron at the S.W. corner of
F.W.Morris's 0.08 acre tract and also being the N.W. corner of Lillian L.
Hites's 0.16 acre tract.

Thence S. 42° - 32' W. 339.00 feet to an iron at the S.W. corner of
Elmer P. Shepard's 0.12 acre tract.

Thence with the north side of a 24 foot driveway N. 54° - 22' W.
201.75 feet to an iron in the center of State Route Number 702.

Thence with the center of State Route Number 702 N. 42° - 30' E. 399.00
feet to the place of beginning.

The above described tract contains 2.31 acres.

Logan County ^{CC} Engineer.



INDEXED ON MAP
3665

-1D-5