

9th Mo. Sept. 22nd 1832 Survey No 190 152

(8776)

John Taylor No 190

Surveyed 50 acres of land for John Taylor
 Beginning at the S.E. corner of Section 30 T 5 R 13
 M.P. a black oak $\text{S } 27^{\circ} \text{ W } 50$ links, a white oak $\text{N } 63^{\circ} \text{ W } 18$ links - thence $\text{N } 59^{\circ} \text{ W}$ with the line between sec.
 29 & 30 164 poles to the 9th sec corner a white oak $\text{N } 33^{\circ} \text{ E } 15$ links - thence $\text{S } 71^{\circ} \text{ E } 47.2$ poles, a kickooy $\text{S } 87^{\circ} \text{ E } 18$ links - thence $\text{S } 89^{\circ} \text{ E } 164$ poles to a stake in the east line of the section, thence with said line $\text{S } 76^{\circ} \text{ W } 49.2$ poles to the beginning containing 50 acres off the south side of the S.E. 9th of said sec.
 John Will
 Richard Meind hall



Chas. W. Harmon 1832


A. Jones
Geo. Pollock
Geo. Camminis
Geo. Shaw
Wm Proctor

9th Mo. Sept. 25th 1832 Survey No 191

(8777)

Surveyed and divided section 29 T 5 R 13 M.P.
 as hereafter described for Jonathan Jones James Pollock George Camminis & William Proctor
 Beginning at the corner of sec 29, 30, 35 & 36 in said T 5 R. original bearing trees standing, a kickooy 8 inches diam $\text{N } 76^{\circ} \text{ E } 14$ links a white oak $\text{S } 12^{\circ} \text{ W } 33$ links, thence between sec 29 & 30 $\text{S } 89^{\circ} \text{ E}$, crossing a branch at 86 poles, passed the original 9th sec corner at 160 poles a W. Oak $\text{S } 20^{\circ} \text{ W } 8$ links, dist a W. Oak $\text{N } 87^{\circ} \text{ E } 18$ links Beginning

320 poles
 found no corner but at the intersection of the original lines I marked a black oak a W. Oak 11 1/2 links a black oak $\text{N } 72^{\circ} \text{ E } 2$ links



thence with the original line between sec 23 and 29 (S 1/4 W 1/4) 346 poles to the corner between sec 22, 23, 28 & 29 one of the original bearing trees standing a hickory 224 N 22 links the other a hickory is down - thence between sections 28 & 29 N 87 1/2 W 320 poles to the corner of sec 28 29 34 & 35 - the old corner trees are all destroyed here - thence between sec 29 & 35 N 10 E 346 poles to the beginning containing 6 1/2 acres - - The 1st division line begins at a stake in the north line, a bur oak N 38 E 18 links on an old N 87 1/2 W 24 links thence S 1/4 W 173 poles to a stake in a cornfield -

2nd The 2nd division line begins at the gr. sec. corner between sec 29 & 35 173 poles from either corner a hickory S 40 E 12 links, a hickory N 87 1/2 W 12 links - thence S 89 1/2 E 160 poles a hickory N 71 1/2 W 17 links a hickory S 53 E 29 links in the center of the section - Continued 100 poles further to the gr. sec. corner between 23 & 29 a red oak N 60 W 14 links a black walnut 65 E 21 links -

3rd The 3rd division line begins at the gr. sec. corner between sec 28 & 29 100 poles from either corner a white oak N 23 1/2 W 8 links - thence N 10 E 173 poles to the center corner -

4th The 4th line begins in the line between sec 28 & 29 80 poles from the SE corner of the sec. a red oak N 75 W 18 links a red oak S 65 E 18 links - thence N 10 E 173 poles to a black oak N 30 W 7 links a hick S 35 E 12 links in the line through the center of the sec -

James Block }
George Shaw } C. W. Mormon 65 1/2

ymos Sept 26 1832 Surveyor 1920
L. Pollock }
Robert Clark } (278) Surveyed and divided the South half of
sec. 22 & 23 R. 13. N. 1/4 for Layton Pollock & Robert
Clark as follows viz: Beginning at the
gr. sec. corner between sec 18 & 24 original bearing
tree yet standing a red oak N 20 E 150 links - thence
with the line between said sec. south 104 poles to
the corner of sec 17, 18, 23 & 24, original bearing trees
standing a red oak N 38 W 13 links, a dog wood N 85 E 26
links